

**LEGEND:**

-  EXISTING CONCRETE OR MASONRY WALL TO BE REFURBISHED
-  New DRY WALL w/ 1/4" thk FICEMBOARD ON BOTH SIDES and 2"x4" WALL FURRING @ 40 cm ON CENTER BOTHWAYS; FULL HEIGHT ; PAINT FIN.
-  NEW 5" THK CHB WALL CEMENT PLASTERED; PAINT FIN. SEE DET @ S-1

**FINISHES :**

FLOOR --- NEW 300mm X 300mm X 3mm HOMOGENEOUS RESILIENT W/ ANTIBAC PROPERTIES VINYL FLOOR TILES ( COLOR :GRAY)

WALLS --- LATEX PAINT FOR ALL CONCRETE OR MASONRY SURFACES ( 3 coats )

CEILING --- 1200mm X 600 mm X 12mm thk. ACOUSTIC CEILING BOARD ON T-RUNNERS ALUM. POWDER COATED (new)


OVERHEAD SHELF-A --- 400 x 600 mm x 5000 mm (3/4" thk.Mar. PLYWOOD, 3 coats Painted) WALL MOUNTED









OVERHEAD SHELF-B --- 400 x 600 mm x 1400 mm (3/4" thk. Mar.PLYWOOD, 3 coats Painted) WALL MOUNTED

PANTRY/STO. --- 300x300x12 mm CERAMIC TILES,

NOTE:  
FURNITURE COST IS NOT INCLUDED IN THE CONTRACT

**1 LAY-OUT PLAN**  
A2 A3 SCALE : 1:100 M

SATISFACTORY TO:  
  
CLEOFE C. ESPINELI  
DICTOR BID-ICT

 <b>ENGINEERING DEPARTMENT</b> PUBLIC WORKS & TECHNICAL SERVICES GROUP BLDG. 256 BARRYMAN ROAD, SUBIC BAY FREEPORT ZONE	CADD BY: 	CHECKED BY: 	REVIEWED BY: 	RECOMMENDED: 	APPROVED: 	PROJECT TITLE: OFFICE RENOVATION AND REHABILITATION OF BID-ICT LOC. BLDG 662 TAFT ST. SBFZ	SHEET NO. A-3 4 of 14
	DESIGNED: 	EDISON D. ICO DIV. CHIEF III PDD	GARY P. FERNANDEZ MANAGER, ENG'G DEPARTMENT	MARCO A. ESTABILLO DA FOR PWTSG	ATTY. WILMA T. EISMA CHAIRMAN & ADMINISTRATOR	 <b>SUBIC BAY METROPOLITAN AUTHORITY</b> SUBIC BAY FREEPORT ZONE	